


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

| | | | | | | | | | | |
|---|------------------|--------------------|--|---|--|---|------------------------------------|-----------------|--------------|---------------|
| APPLICATION FOR PERMIT TO DRILL | | | | | | 1. WELL NAME and NUMBER GMBU M-2-9-15 | | | | |
| 2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/> | | | | | | 3. FIELD OR WILDCAT MONUMENT BUTTE | | | | |
| 4. TYPE OF WELL Oil Well Coalbed Methane Well: NO | | | | | | 5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV) | | | | |
| 6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY | | | | | | 7. OPERATOR PHONE 435 646-4825 | | | | |
| 8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052 | | | | | | 9. OPERATOR E-MAIL mcrozier@newfield.com | | | | |
| 10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) ML-43538 | | | 11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> | | | 12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> | | | | |
| 13. NAME OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 14. SURFACE OWNER PHONE (if box 12 = 'fee') | | | | |
| 15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') | | | | | | 16. SURFACE OWNER E-MAIL (if box 12 = 'fee') | | | | |
| 17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') | | | 18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/> | | | 19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/> | | | | |
| 20. LOCATION OF WELL | | FOOTAGES | | QTR-QTR | SECTION | TOWNSHIP | RANGE | MERIDIAN | | |
| LOCATION AT SURFACE | | 1913 FNL 1641 FWL | | SEnw | 2 | 9.0 S | 15.0 E | S | | |
| Top of Uppermost Producing Zone | | 2401 FNL 2106 FWL | | SEnw | 2 | 9.0 S | 15.0 E | S | | |
| At Total Depth | | 2377 FSL 2492 FEL | | NWSE | 2 | 9.0 S | 15.0 E | S | | |
| 21. COUNTY DUCHESNE | | | 22. DISTANCE TO NEAREST LEASE LINE (Feet) 2377 | | | 23. NUMBER OF ACRES IN DRILLING UNIT 20 | | | | |
| | | | 25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 720 | | | 26. PROPOSED DEPTH MD: 6425 TVD: 6425 | | | | |
| 27. ELEVATION - GROUND LEVEL 5949 | | | 28. BOND NUMBER B001834 | | | 29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478 | | | | |
| Hole, Casing, and Cement Information | | | | | | | | | | |
| String | Hole Size | Casing Size | Length | Weight | Grade & Thread | Max Mud Wt. | Cement | Sacks | Yield | Weight |
| Surf | 12.25 | 8.625 | 0 - 300 | 24.0 | J-55 ST&C | 8.3 | Class G | 138 | 1.17 | 15.8 |
| Prod | 7.875 | 5.5 | 0 - 6425 | 15.5 | J-55 LT&C | 8.3 | Premium Lite High Strength | 306 | 3.26 | 11.0 |
| | | | | | | | 50/50 Poz | 363 | 1.24 | 14.3 |
| ATTACHMENTS | | | | | | | | | | |
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES | | | | | | | | | | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | | | | | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN | | | | | |
| <input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) | | | | | <input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER | | | | | |
| <input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) | | | | | <input checked="" type="checkbox"/> TOPOGRAPHICAL MAP | | | | | |
| NAME Mandie Crozier | | | | TITLE Regulatory Tech | | | PHONE 435 646-4825 | | | |
| SIGNATURE | | | | DATE 07/29/2011 | | | EMAIL mcrozier@newfield.com | | | |
| API NUMBER ASSIGNED 43013509090000 | | | | APPROVAL <div style="text-align: center;">  Permit Manager </div> | | | | | | |

RECEIVED: September 20, 2011

NEWFIELD PRODUCTION COMPANY
GMBU M-2-9-15
AT SURFACE: SE/NW SECTION 2, T9S, R15E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

| | |
|--------------------|--------------|
| Uinta | 0' – 1595' |
| Green River | 1595' |
| Wasatch | 6190' |
| Proposed TD | 6425' |

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1595' – 6190'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

| | |
|--|---|
| Location & Sampled Interval | Date Sampled |
| Flow Rate | Temperature |
| Hardness | pH |
| Water Classification (State of Utah) | Dissolved Calcium (Ca) (mg/l) |
| Dissolved Iron (Fe) (ug/l) | Dissolved Sodium (Na) (mg/l) |
| Dissolved Magnesium (Mg) (mg/l) | Dissolved Carbonate (CO ₃) (mg/l) |
| Dissolved Bicarbonate (NaHCO ₃) (mg/l) | Dissolved Chloride (Cl) (mg/l) |
| Dissolved Sulfate (SO ₄) (mg/l) | Dissolved Total Solids (TDS) (mg/l) |

4. **PROPOSED CASING PROGRAM**

a. **Casing Design: GMBU M-2-9-15**

| Size | Interval | | Weight | Grade | Coupling | Design Factors | | |
|--------------------------|----------|--------|--------|-------|----------|----------------|----------------|------------------|
| | Top | Bottom | | | | Burst | Collapse | Tension |
| Surface casing 8-5/8" | 0' | 300' | 24.0 | J-55 | STC | 2,950 17.53 | 1,370 14.35 | 244,000 33.89 |
| Prod casing 5-1/2" | 0' | 6,425' | 15.5 | J-55 | LTC | 4,810 2.35 | 4,040 1.98 | 217,000 2.18 |

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. **Cementing Design: GMBU M-2-9-15**

| Job | Fill | Description | Sacks | OH Excess* | Weight (ppg) | Yield (ft ³ /sk) |
|---------------------|--------|-------------------------------------|-----------------|---------------|-----------------|--------------------------------|
| | | | ft ³ | | | |
| Surface casing | 300' | Class G w/ 2% CaCl | 138 161 | 30% | 15.8 | 1.17 |
| Prod casing Lead | 4,425' | Prem Lite II w/ 10% gel + 3% KCl | 306 997 | 30% | 11.0 | 3.26 |
| Prod casing Tail | 2,000' | 50/50 Poz w/ 2% gel + 3% KCl | 363 451 | 30% | 14.3 | 1.24 |

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 300 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 300 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.


9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the third quarter of 2011, and take approximately seven (7) days from spud to rig release.

T9S, R15E, S.L.B.&M.



◆ = SECTION CORNERS LOCATED


BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

M-2-9-15
(Surface Location) **NAD 83**
LATITUDE = 40° 03' 43.09"
LONGITUDE = 110° 12' 07.88"

NEWFIELD EXPLORATION COMPANY

WELL LOCATION, M-2-9-15, LOCATED AS SHOWN IN THE SE 1/4 NW 1/4 OF SECTION 2, T9S, R15E, S.L.B.&M. DUCHESNE COUNTY, UTAH.


TARGET BOTTOM HOLE, M-2-9-15, LOCATED AS SHOWN IN THE NW 1/4 SE 1/4 OF SECTION 2, T9S, R15E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



WELL LOCATION: M-2-9-15

ELEV. EXIST. GRADED GROUND = 5949'

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.




TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------|
| DATE SURVEYED: 06-03-11 | SURVEYED BY: D.G. | VERSION: |
| DATE DRAWN: 07-06-11 | DRAWN BY: M.W. | V1 |
| REVISED: | SCALE: 1" = 1000' | |

Access Road Map



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

N



NEWFIELD EXPLORATION COMPANY

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)

SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.


| | | | |
|-----------|------------|----------|----------|
| DRAWN BY: | C.H.M. | REVISED: | VERSION: |
| DATE: | 07-15-2011 | | V1 |
| SCALE: | 1:100,000 | | |

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

 Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

N

**NEWFIELD EXPLORATION COMPANY**

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)

SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.

| | | | |
|-----------|-------------|----------|-----------|
| DRAWN BY: | C.H.M. | REVISED: | VERSION: |
| DATE: | 07-15-2011 | | V1 |
| SCALE: | 1" = 2,000' | | |

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)

Existing
Flowline

Existing
Gas Pipeline

Legend

Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

N



NEWFIELD EXPLORATION COMPANY

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)

SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.

| | | | |
|-----------|-------------|----------|----------|
| DRAWN BY: | C.H.M. | REVISED: | VERSION: |
| DATE: | 07-15-2011 | | V1 |
| SCALE: | 1" = 2,000' | | |

TOPOGRAPHIC MAP

SHEET

C




Exhibit "B" Map

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)

Legend

○ 1 Mile Radius

● Pad Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

N

**NEWFIELD EXPLORATION COMPANY**

6-2-9-15 (Existing Well)
H-2-9-15 (Proposed Well)
M-2-9-15 (Proposed Well)
SEC. 2, T9S, R15E, S.L.B.&M. Duchesne County, UT.

| | | | |
|-----------|-------------|----------|----------|
| DRAWN BY: | C.H.M. | REVISED: | VERSION: |
| DATE: | 07-15-2011 | | V1 |
| SCALE: | 1" = 2,000' | | |

TOPOGRAPHIC MAP

SHEET

D



NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 2 T9, R15

M-2-9-15

Wellbore #1

Plan: Design #1

Standard Planning Report

08 July, 2011





| | | | |
|------------------|----------------------------|-------------------------------------|------------------------------------|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well M-2-9-15 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Project: | USGS Myton SW (UT) | MD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Site: | SECTION 2 T9, R15 | North Reference: | True |
| Well: | M-2-9-15 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| | | | |
|--------------------|--|----------------------|----------------|
| Project | USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA | | |
| Map System: | US State Plane 1983 | System Datum: | Mean Sea Level |
| Geo Datum: | North American Datum 1983 | | |
| Map Zone: | Utah Central Zone | | |

| | | | | |
|------------------------------|-------------------|---------------------|-----------------|-------------------------------------|
| Site | SECTION 2 T9, R15 | | | |
| Site Position: | | Northing: | 7,191,145.41 ft | Latitude: 40° 3' 15.350 N |
| From: | Lat/Long | Easting: | 2,005,088.49 ft | Longitude: 110° 11' 49.770 W |
| Position Uncertainty: | 0.0 ft | Slot Radius: | " | Grid Convergence: 0.83 ° |

| | | | | |
|-----------------------------|--|-------------|----------------------------|-----------------|
| Well | M-2-9-15, SHL LAT: 40 03 43.09 LONG: -110 12 07.88 | | | |
| Well Position | +N/-S | 2,806.8 ft | Northing: | 7,193,931.43 ft |
| | +E/-W | -1,408.1 ft | Easting: | 2,003,639.78 ft |
| Position Uncertainty | | 0.0 ft | Wellhead Elevation: | 5,961.0 ft |
| | | | Ground Level: | 5,949.0 ft |

| | | | | | |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| Wellbore | Wellbore #1 | | | | |
| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
| | IGRF2010 | 2011/06/25 | 11.37 | 65.78 | 52,254 |

| | | | | |
|--------------------------|------------------------------|-------------------|----------------------|----------------------|
| Design | Design #1 | | | |
| Audit Notes: | | | | |
| Version: | Phase: | PROTOTYPE | Tie On Depth: | 0.0 |
| Vertical Section: | Depth From (TVD) (ft) | +N/-S (ft) | +E/-W (ft) | Direction (°) |
| | 0.0 | 0.0 | 0.0 | 136.36 |

| Plan Sections | | | | | | | | | | |
|----------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|----------------------|---------------------|---------|--------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1,601.4 | 15.02 | 136.36 | 1,589.9 | -94.4 | 90.1 | 1.50 | 1.50 | 0.00 | 136.36 | |
| 5,132.1 | 15.02 | 136.36 | 5,000.0 | -756.7 | 721.6 | 0.00 | 0.00 | 0.00 | 0.00 | M-2-9-15 TGT |
| 6,426.3 | 15.02 | 136.36 | 6,250.0 | -999.4 | 953.0 | 0.00 | 0.00 | 0.00 | 0.00 | |



| | | | |
|------------------|----------------------------|-------------------------------------|------------------------------------|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well M-2-9-15 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Project: | USGS Myton SW (UT) | MD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Site: | SECTION 2 T9, R15 | North Reference: | True |
| Well: | M-2-9-15 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| Planned Survey | | | | | | | | | |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 100.0 | 0.00 | 0.00 | 100.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 200.0 | 0.00 | 0.00 | 200.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 300.0 | 0.00 | 0.00 | 300.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 400.0 | 0.00 | 0.00 | 400.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 500.0 | 0.00 | 0.00 | 500.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.00 |
| 700.0 | 1.50 | 136.36 | 700.0 | -0.9 | 0.9 | 1.3 | 1.50 | 1.50 | 0.00 |
| 800.0 | 3.00 | 136.36 | 799.9 | -3.8 | 3.6 | 5.2 | 1.50 | 1.50 | 0.00 |
| 900.0 | 4.50 | 136.36 | 899.7 | -8.5 | 8.1 | 11.8 | 1.50 | 1.50 | 0.00 |
| 1,000.0 | 6.00 | 136.36 | 999.3 | -15.1 | 14.4 | 20.9 | 1.50 | 1.50 | 0.00 |
| 1,100.0 | 7.50 | 136.36 | 1,098.6 | -23.6 | 22.6 | 32.7 | 1.50 | 1.50 | 0.00 |
| 1,200.0 | 9.00 | 136.36 | 1,197.5 | -34.0 | 32.5 | 47.0 | 1.50 | 1.50 | 0.00 |
| 1,300.0 | 10.50 | 136.36 | 1,296.1 | -46.3 | 44.1 | 64.0 | 1.50 | 1.50 | 0.00 |
| 1,400.0 | 12.00 | 136.36 | 1,394.2 | -60.4 | 57.6 | 83.5 | 1.50 | 1.50 | 0.00 |
| 1,500.0 | 13.50 | 136.36 | 1,491.7 | -76.4 | 72.8 | 105.5 | 1.50 | 1.50 | 0.00 |
| 1,601.4 | 15.02 | 136.36 | 1,589.9 | -94.4 | 90.1 | 130.5 | 1.50 | 1.50 | 0.00 |
| 1,700.0 | 15.02 | 136.36 | 1,685.2 | -112.9 | 107.7 | 156.1 | 0.00 | 0.00 | 0.00 |
| 1,800.0 | 15.02 | 136.36 | 1,781.8 | -131.7 | 125.6 | 182.0 | 0.00 | 0.00 | 0.00 |
| 1,900.0 | 15.02 | 136.36 | 1,878.4 | -150.5 | 143.5 | 207.9 | 0.00 | 0.00 | 0.00 |
| 2,000.0 | 15.02 | 136.36 | 1,974.9 | -169.2 | 161.4 | 233.8 | 0.00 | 0.00 | 0.00 |
| 2,100.0 | 15.02 | 136.36 | 2,071.5 | -188.0 | 179.3 | 259.7 | 0.00 | 0.00 | 0.00 |
| 2,200.0 | 15.02 | 136.36 | 2,168.1 | -206.7 | 197.1 | 285.7 | 0.00 | 0.00 | 0.00 |
| 2,300.0 | 15.02 | 136.36 | 2,264.7 | -225.5 | 215.0 | 311.6 | 0.00 | 0.00 | 0.00 |
| 2,400.0 | 15.02 | 136.36 | 2,361.3 | -244.2 | 232.9 | 337.5 | 0.00 | 0.00 | 0.00 |
| 2,500.0 | 15.02 | 136.36 | 2,457.9 | -263.0 | 250.8 | 363.4 | 0.00 | 0.00 | 0.00 |
| 2,600.0 | 15.02 | 136.36 | 2,554.4 | -281.7 | 268.7 | 389.3 | 0.00 | 0.00 | 0.00 |
| 2,700.0 | 15.02 | 136.36 | 2,651.0 | -300.5 | 286.6 | 415.2 | 0.00 | 0.00 | 0.00 |
| 2,800.0 | 15.02 | 136.36 | 2,747.6 | -319.3 | 304.5 | 441.2 | 0.00 | 0.00 | 0.00 |
| 2,900.0 | 15.02 | 136.36 | 2,844.2 | -338.0 | 322.3 | 467.1 | 0.00 | 0.00 | 0.00 |
| 3,000.0 | 15.02 | 136.36 | 2,940.8 | -356.8 | 340.2 | 493.0 | 0.00 | 0.00 | 0.00 |
| 3,100.0 | 15.02 | 136.36 | 3,037.4 | -375.5 | 358.1 | 518.9 | 0.00 | 0.00 | 0.00 |
| 3,200.0 | 15.02 | 136.36 | 3,133.9 | -394.3 | 376.0 | 544.8 | 0.00 | 0.00 | 0.00 |
| 3,300.0 | 15.02 | 136.36 | 3,230.5 | -413.0 | 393.9 | 570.7 | 0.00 | 0.00 | 0.00 |
| 3,400.0 | 15.02 | 136.36 | 3,327.1 | -431.8 | 411.8 | 596.7 | 0.00 | 0.00 | 0.00 |
| 3,500.0 | 15.02 | 136.36 | 3,423.7 | -450.5 | 429.7 | 622.6 | 0.00 | 0.00 | 0.00 |
| 3,600.0 | 15.02 | 136.36 | 3,520.3 | -469.3 | 447.5 | 648.5 | 0.00 | 0.00 | 0.00 |
| 3,700.0 | 15.02 | 136.36 | 3,616.9 | -488.1 | 465.4 | 674.4 | 0.00 | 0.00 | 0.00 |
| 3,800.0 | 15.02 | 136.36 | 3,713.4 | -506.8 | 483.3 | 700.3 | 0.00 | 0.00 | 0.00 |
| 3,900.0 | 15.02 | 136.36 | 3,810.0 | -525.6 | 501.2 | 726.2 | 0.00 | 0.00 | 0.00 |
| 4,000.0 | 15.02 | 136.36 | 3,906.6 | -544.3 | 519.1 | 752.2 | 0.00 | 0.00 | 0.00 |
| 4,100.0 | 15.02 | 136.36 | 4,003.2 | -563.1 | 537.0 | 778.1 | 0.00 | 0.00 | 0.00 |
| 4,200.0 | 15.02 | 136.36 | 4,099.8 | -581.8 | 554.9 | 804.0 | 0.00 | 0.00 | 0.00 |
| 4,300.0 | 15.02 | 136.36 | 4,196.4 | -600.6 | 572.7 | 829.9 | 0.00 | 0.00 | 0.00 |
| 4,400.0 | 15.02 | 136.36 | 4,292.9 | -619.4 | 590.6 | 855.8 | 0.00 | 0.00 | 0.00 |
| 4,500.0 | 15.02 | 136.36 | 4,389.5 | -638.1 | 608.5 | 881.7 | 0.00 | 0.00 | 0.00 |
| 4,600.0 | 15.02 | 136.36 | 4,486.1 | -656.9 | 626.4 | 907.7 | 0.00 | 0.00 | 0.00 |
| 4,700.0 | 15.02 | 136.36 | 4,582.7 | -675.6 | 644.3 | 933.6 | 0.00 | 0.00 | 0.00 |
| 4,800.0 | 15.02 | 136.36 | 4,679.3 | -694.4 | 662.2 | 959.5 | 0.00 | 0.00 | 0.00 |
| 4,900.0 | 15.02 | 136.36 | 4,775.9 | -713.1 | 680.1 | 985.4 | 0.00 | 0.00 | 0.00 |
| 5,000.0 | 15.02 | 136.36 | 4,872.4 | -731.9 | 697.9 | 1,011.3 | 0.00 | 0.00 | 0.00 |
| 5,100.0 | 15.02 | 136.36 | 4,969.0 | -750.6 | 715.8 | 1,037.2 | 0.00 | 0.00 | 0.00 |
| 5,132.1 | 15.02 | 136.36 | 5,000.0 | -756.7 | 721.6 | 1,045.5 | 0.00 | 0.00 | 0.00 |
| M-2-9-15 TGT | | | | | | | | | |




| | | | |
|------------------|----------------------------|-------------------------------------|------------------------------------|
| Database: | EDM 2003.21 Single User Db | Local Co-ordinate Reference: | Well M-2-9-15 |
| Company: | NEWFIELD EXPLORATION | TVD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Project: | USGS Myton SW (UT) | MD Reference: | M-2-9-15 @ 5961.0ft (Newfield Rig) |
| Site: | SECTION 2 T9, R15 | North Reference: | True |
| Well: | M-2-9-15 | Survey Calculation Method: | Minimum Curvature |
| Wellbore: | Wellbore #1 | | |
| Design: | Design #1 | | |

| Planned Survey | | | | | | | | | | |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|--|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | |
| 5,200.0 | 15.02 | 136.36 | 5,065.6 | -769.4 | 733.7 | 1,063.2 | 0.00 | 0.00 | 0.00 | |
| 5,300.0 | 15.02 | 136.36 | 5,162.2 | -788.2 | 751.6 | 1,089.1 | 0.00 | 0.00 | 0.00 | |
| 5,400.0 | 15.02 | 136.36 | 5,258.8 | -806.9 | 769.5 | 1,115.0 | 0.00 | 0.00 | 0.00 | |
| 5,500.0 | 15.02 | 136.36 | 5,355.4 | -825.7 | 787.4 | 1,140.9 | 0.00 | 0.00 | 0.00 | |
| 5,600.0 | 15.02 | 136.36 | 5,451.9 | -844.4 | 805.3 | 1,166.8 | 0.00 | 0.00 | 0.00 | |
| 5,700.0 | 15.02 | 136.36 | 5,548.5 | -863.2 | 823.1 | 1,192.7 | 0.00 | 0.00 | 0.00 | |
| 5,800.0 | 15.02 | 136.36 | 5,645.1 | -881.9 | 841.0 | 1,218.7 | 0.00 | 0.00 | 0.00 | |
| 5,900.0 | 15.02 | 136.36 | 5,741.7 | -900.7 | 858.9 | 1,244.6 | 0.00 | 0.00 | 0.00 | |
| 6,000.0 | 15.02 | 136.36 | 5,838.3 | -919.4 | 876.8 | 1,270.5 | 0.00 | 0.00 | 0.00 | |
| 6,100.0 | 15.02 | 136.36 | 5,934.9 | -938.2 | 894.7 | 1,296.4 | 0.00 | 0.00 | 0.00 | |
| 6,200.0 | 15.02 | 136.36 | 6,031.4 | -957.0 | 912.6 | 1,322.3 | 0.00 | 0.00 | 0.00 | |
| 6,300.0 | 15.02 | 136.36 | 6,128.0 | -975.7 | 930.5 | 1,348.2 | 0.00 | 0.00 | 0.00 | |
| 6,400.0 | 15.02 | 136.36 | 6,224.6 | -994.5 | 948.3 | 1,374.2 | 0.00 | 0.00 | 0.00 | |
| 6,426.3 | 15.02 | 136.36 | 6,250.0 | -999.4 | 953.0 | 1,381.0 | 0.00 | 0.00 | 0.00 | |





Project: USGS Myton SW (UT)
 Site: SECTION 2 T9, R15
 Well: M-2-9-15
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 11.37°

Magnetic Field
 Strength: 52253.6snT
 Dip Angle: 65.78°
 Date: 2011/06/25
 Model: IGRF2010

KOP @ 600'
 DOGLEG RATE 1.5 DEG/100
 TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

| Name | TVD | +N/-S | +E/-W | Shape |
|--------------|--------|--------|-------|-----------------------|
| M-2-9-15 TGT | 5000.0 | -756.7 | 721.6 | Circle (Radius: 75.0) |

SECTION DETAILS

| Sec | MD | Inc | Azi | TVD | +N/-S | +E/-W | DLeg | TFace | VSec | Target |
|-----|--------|-------|--------|--------|--------|-------|------|--------|--------|--------------|
| 1 | 0.0 | 0.00 | 0.00 | 0.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.0 | |
| 2 | 600.0 | 0.00 | 0.00 | 600.0 | 0.0 | 0.0 | 0.00 | 0.00 | 0.0 | |
| 3 | 1601.4 | 15.02 | 136.36 | 1589.9 | -94.4 | 90.1 | 1.50 | 136.36 | 130.5 | |
| 4 | 5132.1 | 15.02 | 136.36 | 5000.0 | -756.7 | 721.6 | 0.00 | 0.00 | 1045.5 | M-2-9-15 TGT |
| 5 | 6426.3 | 15.02 | 136.36 | 6250.0 | -999.4 | 953.0 | 0.00 | 0.00 | 1381.0 | |



**NEWFIELD PRODUCTION COMPANY
GMBU M-2-9-15
AT SURFACE: SE/NW SECTION 2, T9S, R15E
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU M-2-9-15 located in the SE 1/4 NW 1/4 Section 2, T9S, R15E, Duchesen County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed southwesterly - 6.4 miles \pm to it's junction with an existing road to the southwest; proceed southwesterly - 2.4 miles \pm to it's junction with an existing road to the southwest; proceed southwesterly - 0.8 miles \pm to it's junction with an existing road to the southeast; proceed southeasterly - 1.6 miles \pm to it's junction with an existing road to the southwest; proceed southwesterly - 1.2 miles \pm to it's junction with an existing road to the northwest; proceed northwesterly - 0.4 miles \pm to it's junction with an existing road to the west; proceed westerly and then southwesterly - 0.2 miles \pm to the existing 6-2-9-15 well pad.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 6-2-9-15 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – State of Utah.

11. **OTHER ADDITIONAL INFORMATION :**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit #U-03-MQ-0751b,s 11/18/03, prepared by Montgomery Archaeological Consultants. Paleontological Resource Survey prepared by, Wade E. Miller, 7/28/03. See attached report cover pages, Exhibit "D".

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the GMBU M-2-9-15, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU M-2-9-15, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

Representative

Name: Tim Eaton

Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #M-2-9-15, Section 2, Township 9S, Range 15E: Lease ML-43538 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #B001834.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

7/29/11
Date

Mandie Crozier
Regulatory Specialist
Newfield Production Company

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

NEWFIELD EXPLORATION COMPANY

WELL PAD INTERFERENCE PLAT

- 6-2-9-15 (Existing Well)
- H-2-9-15 (Proposed Well)
- M-2-9-15 (Proposed Well)

Pad Location: SENW Section 2, T9S, R15E, S.L.B.&M.



TOP HOLE FOOTAGES

- H-2-9-15 (PROPOSED)
1893' FNL & 3428' FEL
- M-2-9-15 (PROPOSED)
1913' FNL & 3433' FEL

CENTER OF PATTERN FOOTAGES

- H-2-9-15 (PROPOSED)
1320' FSL & 2700' FEL
- M-2-9-15 (PROPOSED)
2680' FNL & 2720' FEL


- ### BOTTOM HOLE FOOTAGES
- H-2-9-15 (PROPOSED)
1171' FNL & 2510' FEL
 - M-2-9-15 (PROPOSED)
2377' FSL & 2492' FEL

RELATIVE COORDINATES From Top Hole to Bottom Hole

| WELL | NORTH | EAST |
|----------|-------|------|
| H-2-9-15 | 583' | 721' |
| M-2-9-15 | -757' | 722' |

RELATIVE COORDINATES From Top Hole to C.O.P.

| WELL | NORTH | EAST |
|----------|-------|------|
| H-2-9-15 | 735' | 909' |
| M-2-9-15 | -999' | 953' |



LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

| WELL | LATITUDE | LONGITUDE |
|----------|----------------|-----------------|
| 6-2-9-15 | 40° 03' 43.49" | 110° 12' 07.75" |
| H-2-9-15 | 40° 03' 43.29" | 110° 12' 07.81" |
| M-2-9-15 | 40° 03' 43.09" | 110° 12' 07.88" |

SURVEYED BY: D.G.

DATE SURVEYED: 06-03-11

DRAWN BY: M.W.

DATE DRAWN: 07-06-11

SCALE: 1" = 60'

REVISED:

VERSION: V1

Tri State
Land Surveying, Inc.

(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

| | | | |
|-------------------|-------------------------|----------|--|
| SURVEYED BY: D.G. | DATE SURVEYED: 06-03-11 | VERSION: |  Tri State Land Surveying, Inc. (435) 781-2501 180 NORTH VERNAL AVE. VERNAL, UTAH 84078 |
| DRAWN BY: M.W. | DATE DRAWN: 07-11-11 | V1 | |
| SCALE: 1" = 60' | REVISED: | | |

NEWFIELD EXPLORATION COMPANY





CROSS SECTIONS

6-2-9-15 (Existing Well)

H-2-9-15 (Proposed Well)

M-2-9-15 (Proposed Well)

Pad Location: SENW Section 2, T9S, R15E, S.L.B.&M.



NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

| ITEM | CUT | FILL | 6" TOPSOIL | EXCESS |
|--------|-------|------|--|--------|
| PAD | 1,530 | 50 | Topsoil is not included in Pad Cut | 1,480 |
| PIT | 690 | 0 | | 690 |
| TOTALS | 2,220 | 50 | 400 | 2,170 |

| | | |
|-------------------|-------------------------|----------|
| SURVEYED BY: D.G. | DATE SURVEYED: 06-03-11 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 07-11-11 | V1 |
| SCALE: 1" = 60' | REVISED: | |

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

NEWFIELD EXPLORATION COMPANY


TYPICAL RIG LAYOUT

6-2-9-15 (Existing Well)

H-2-9-15 (Proposed Well)


M-2-9-15 (Proposed Well)

Pad Location: SENW Section 2, T9S, R15E, S.L.B.&M.



| | | |
|-------------------|-------------------------|----------|
| SURVEYED BY: D.G. | DATE SURVEYED: 06-03-11 | VERSION: |
| DRAWN BY: M.W. | DATE DRAWN: 07-11-11 | V1 |
| SCALE: 1" = 60' | REVISED: | |


Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501



API Number: 4301350909
Well Name: GMBU M-2-9-15
Township T0.9 . Range R1.5 . Section 02
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
 Map Produced by Diana Mason

| Units | Wells Query |
|---------------|------------------------------------|
| STATUS | Status |
| ACTIVE | APD - Approved Permit |
| EXPLORATORY | DRL - Spudded (Drilling Commenced) |
| GAS STORAGE | GIW - Gas Injection |
| NF PP OIL | GS - Gas Storage |
| NF SECONDARY | LA - Location Abandoned |
| PI OIL | LOC - New Location |
| PP GAS | OPS - Operation Suspended |
| PP GEOTHERMAL | PA - Plugged Abandoned |
| PP OIL | PGW - Producing Gas Well |
| SECONDARY | POW - Producing Oil Well |
| TERMINATED | RET - Returned APD |
| Fields | Fields |
| Unknown | SGW - Shut-in Gas Well |
| ABANDONED | SOW - Shut-in Oil Well |
| ACTIVE | TA - Temp. Abandoned |
| COMBINED | TW - Test Well |
| INACTIVE | WDW - Water Disposal |
| STORAGE | WIW - Water Injection Well |
| TERMINATED | WSW - Water Supply Well |
| Sections | |
| Township | |



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

August 3, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2011 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

| API # | WELL NAME | LOCATION |
|---------------------------|---------------|--|
| (Proposed PZ GREEN RIVER) | | |
| 43-013-50906 | GMBU R-2-9-15 | Sec 02 T09S R15E 0561 FSL 2050 FWL BHL Sec 02 T09S R15E 1367 FSL 2620 FEL |
| 43-013-50907 | GMBU L-2-9-15 | Sec 02 T09S R15E 1977 FNL 2241 FEL BHL Sec 02 T09S R15E 2357 FSL 1068 FEL |
| 43-013-50908 | GMBU H-2-9-15 | Sec 02 T09S R15E 1893 FNL 1639 FWL BHL Sec 02 T09S R15E 1171 FNL 2510 FEL |
| 43-013-50909 | GMBU M-2-9-15 | Sec 02 T09S R15E 1913 FNL 1641 FWL BHL Sec 02 T09S R15E 2377 FSL 2492 FEL |
| 43-013-50910 | GMBU N-2-9-15 | Sec 02 T09S R15E 2015 FSL 2037 FWL BHL Sec 02 T09S R15E 2615 FNL 1043 FWL |
| 43-013-50911 | GMBU Q-2-9-15 | Sec 02 T09S R15E 2001 FSL 2053 FWL BHL Sec 02 T09S R15E 0994 FSL 1106 FWL |

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2011.08.03 14:18:49 -06'00'

RECEIVED: August 04, 2011

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:8-3-11



VIA ELECTRONIC DELIVERY

August 9, 2011

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
GMBU M-2-9-15
Greater Monument Butte (Green River) Unit

Surface Hole: T9S-R15E Section 2: SENW (ML-43538)
1913' FNL 1641' FWL

At Target: T9S-R15E Section 2: NWSE (ML-43538)
2377' FSL 2492' FEL

Duchesne County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 7/28/2011, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4153 or by email at pburns@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink, appearing to read "P. Burns".

Peter Burns
Land Associate

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

| APPLICATION FOR PERMIT TO DRILL | | | | 5. MINERAL LEASE NO: ML-43538 | 6. SURFACE: State |
|--|--|--|---------------------------------|---|----------------------|
| 1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> | | | | 7. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA | |
| B. TYPE OF WELL: OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> | | | | 8. UNIT or CA AGREEMENT NAME: Greater Monument Butte | |
| 2. NAME OF OPERATOR: Newfield Production Company | | | | 9. WELL NAME and NUMBER: GMBU M-2-9-15 | |
| 3. ADDRESS OF OPERATOR: Route #3 Box 3630 CITY Myton STATE UT ZIP 84052 | | | PHONE NUMBER: (435) 646-3721 | | |
| 4. LOCATION OF WELL (FOOTAGES) AT SURFACE: SE/NW 1913' FNL 1641' FWL Sec. 2 T9S R15E AT PROPOSED PRODUCING ZONE: NW/SE 2377' FSL 2492' FEL Sec. 2 T9S R15E | | | | 10. FIELD AND POOL, OR WILDCAT: Monument Butte | |
| 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SE/NW 2 9S 15E | | | | | |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 14.3 miles southwest of Myton, Utah | | | | 12. COUNTY: Duchesne | 13. STATE: UTAH |
| 15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) Approx. 2377' f/lse line, NA' f/unit line | | 16. NUMBER OF ACRES IN LEASE: 621.07 acres | | 17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 20 acres | |
| 18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) Approx. 720' | | 19. PROPOSED DEPTH: 6,425 | | 20. BOND DESCRIPTION: #B001834 | |
| 21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5949' GL | | 22. APPROXIMATE DATE WORK WILL START: 3rd Qtr. 2011 | | 23. ESTIMATED DURATION: (15) days from SPUD to rig release | |

24.

PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | CASING SIZE, GRADE, AND WEIGHT PER FOOT | SETTING DEPTH | CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT |
|--------------|---|---------------|---|
| 12 1/4 | 8 5/8 J-55 24.0 | 300 | Class G w/2% CaCl 138 sx +/- 1.17 15.8 |
| 7 7/8 | 5 1/2 J-55 15.5 | 6,425 | Lead(Prem Lite II) 306 sx +/- 3.26 11.0 |
| | | | Tail (50/50 Poz) 363 sx +/- 1.24 14.3 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

25.

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- ☒ WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER
☒ EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER

- ☒ COMPLETE DRILLING PLAN
☐ FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Mandie CrozierTITLE Regulatory SpecialistSIGNATURE Mandie CrozierDATE 7/23/11


(This space for State use only)

API NUMBER ASSIGNED: _____

APPROVAL: _____

NEWFIELD EXPLORATION COMPANY

T9S, R15E, S.L.B.&M.



WELL LOCATION, M-2-9-15, LOCATED AS SHOWN IN THE SE 1/4 NW 1/4 OF SECTION 2, T9S, R15E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, M-2-9-15, LOCATED AS SHOWN IN THE NW 1/4 SE 1/4 OF SECTION 2, T9S, R15E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

WELL LOCATION:
M-2-9-15
ELEV. EXIST. GRADED GROUND = 5949'

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


REGISTERED LAND SURVEYOR
STACY W. STEWART
07-18-11
REGISTRATION NO. 189377
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|----------------------------|-------------------|----------------|
| DATE SURVEYED: 06-03-11 | SURVEYED BY: D.G. | VERSION: V1 |
| DATE DRAWN: 07-06-11 | DRAWN BY: M.W. | |
| REVISED: | SCALE: 1" = 1000' | |

M-2-9-15
(Surface Location) NAD 83
LATITUDE = 40° 03' 43.09"
LONGITUDE = 110° 12' 07.88"

SECTION CORNERS LOCATED
BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'



| | | | | |
|--|---|-------|--|--|
| Well Name | NEWFIELD PRODUCTION COMPANY GMBU M-2-9-15 43013 | | | |
| String | Surf | Prod | | |
| Casing Size(") | 8.625 | 5.500 | | |
| Setting Depth (TVD) | 300 | 6249 | | |
| Previous Shoe Setting Depth (TVD) | 0 | 300 | | |
| Max Mud Weight (ppg) | 8.3 | 8.4 | | |
| BOPE Proposed (psi) | 500 | 2000 | | |
| Casing Internal Yield (psi) | 2950 | 4810 | | |
| Operators Max Anticipated Pressure (psi) | 2706 | 8.3 | | |

| | | | |
|---|--|-------|---|
| Calculations | Surf String | 8.625 | " |
| Max BHP (psi) | .052*Setting Depth*MW= | 129 | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | 93 | YES air drill |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | 63 | YES OK |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | 63 | NO OK |
| Required Casing/BOPE Test Pressure= | | 300 | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | 0 | psi *Assumes 1psi/ft frac gradient |

| | | | |
|---|--|-------|---|
| Calculations | Prod String | 5.500 | " |
| Max BHP (psi) | .052*Setting Depth*MW= | 2730 | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | 1980 | YES |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | 1355 | YES OK |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | 1421 | NO Reasonable for area |
| Required Casing/BOPE Test Pressure= | | 2000 | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | 300 | psi *Assumes 1psi/ft frac gradient |

| | | | |
|---|--|--|---|
| Calculations | String | | " |
| Max BHP (psi) | .052*Setting Depth*MW= | | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | | NO |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | | NO |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | | NO |
| Required Casing/BOPE Test Pressure= | | | psi |
| *Max Pressure Allowed @ Previous Casing Shoe= | | | psi *Assumes 1psi/ft frac gradient |

| | | | |
|-------------------------------------|--|--|---|
| Calculations | String | | " |
| Max BHP (psi) | .052*Setting Depth*MW= | | |
| | | | BOPE Adequate For Drilling And Setting Casing at Depth? |
| MASP (Gas) (psi) | Max BHP-(0.12*Setting Depth)= | | NO |
| MASP (Gas/Mud) (psi) | Max BHP-(0.22*Setting Depth)= | | NO |
| | | | *Can Full Expected Pressure Be Held At Previous Shoe? |
| Pressure At Previous Shoe | Max BHP-.22*(Setting Depth - Previous Shoe Depth)= | | NO |
| Required Casing/BOPE Test Pressure= | | | psi |

API Well Number: 43013509090000


*Max Pressure Allowed @ Previous Casing Shoe=

psi *Assumes 1psi/ft frac gradient

RECEIVED: September 20, 2011

43013509090000 GMBU M-2-9-15

Casing Schematic



| | | |
|--------------|-------------------------------------|-----------------------------|
| Well name: | 43013509090000 GMBU M-2-9-15 | |
| Operator: | NEWFIELD PRODUCTION COMPANY | |
| String type: | Surface | Project ID: 43-013-50909 |
| Location: | DUCHESE COUNTY | |

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 78 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 80 ft

Burst

Max anticipated surface pressure: 264 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 262 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 6,249 ft
Next mud weight: 8.400 ppg
Next setting BHP: 2,727 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure: 300 psi

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Est. Cost (\$) |
|---------|---------------------|-----------|-------------------------|-------|------------|----------------------|---------------------|---------------------|----------------|
| 1 | 300 | 8.625 | 24.00 | J-55 | ST&C | 300 | 300 | 7.972 | 1544 |

| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (kips) | Tension Strength (kips) | Tension Design Factor |
|---------|---------------------|-------------------------|------------------------|------------------|----------------------|---------------------|---------------------|-------------------------|-----------------------|
| 1 | 130 | 1370 | 10.557 | 300 | 2950 | 9.83 | 7.2 | 244 | 33.90 J |

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 18, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

| | | |
|--------------|-------------------------------------|-----------------------------|
| Well name: | 43013509090000 GMBU M-2-9-15 | |
| Operator: | NEWFIELD PRODUCTION COMPANY | |
| String type: | Production | Project ID: 43-013-50909 |
| Location: | DUCHESNE COUNTY | |

Design parameters:**Collapse**

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 161 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 842 ft

Burst

Max anticipated surface pressure: 1,352 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 2,727 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 5,603 ft

Directional Info - Build & Hold

Kick-off point 600 ft
Departure at shoe: 1381 ft
Maximum dogleg: 1.5 °/100ft
Inclination at shoe: 15.02 °

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Est. Cost (\$) |
|---------|---------------------|-------------------------|-------------------------|------------------|----------------------|----------------------|---------------------|-------------------------|-----------------------|
| 1 | 6425 | 5.5 | 15.50 | J-55 | LT&C | 6249 | 6425 | 4.825 | 22687 |
| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (kips) | Tension Strength (kips) | Tension Design Factor |
| 1 | 2727 | 4040 | 1.482 | 2727 | 4810 | 1.76 | 96.9 | 217 | 2.24 J |

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: August 18, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6249 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

From: Jim Davis
To: Hill, Brad; Mason, Diana
CC: Bonner, Ed; Garrison, LaVonne; mcrozier@newfield.com; teaton@newfield...
Date: 9/20/2011 3:45 PM
Subject: Newfield APD approvals

The following APDs have been approved by SITLA including arch and paleo clearance.

4304751877 GMBU I-32-8-18
4304751878 GMBU H-32-8-18
4304751879 GMBU L-32-8-18
4304751880 GMBU R-32-8-18
4304751881 GMBU M-32-8-18
4304751882 GMBU G-32-8-18
4304751883 GMBU N-32-8-18
4304751884 GMBU S-32-8-18
4301350898 GMBU 1-2-9-15H
4301350906 GMBU R-2-9-15
4301350907 GMBU L-2-9-15
4301350908 GMBU H-2-9-15
4301350909 GMBU M-2-9-15
4301350910 GMBU N-2-9-15
4301350911 GMBU Q-2-9-15

Thanks.

-Jim

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

RECEIVED: September 20, 2011

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

| | | | | | |
|--------------------------|-----------------------------|---------------|-------|-------------------|----------------|
| Operator | NEWFIELD PRODUCTION COMPANY | | | | |
| Well Name | GMBU M-2-9-15 | | | | |
| API Number | 43013509090000 | APD No | 4289 | Field/Unit | MONUMENT BUTTE |
| Location: 1/4,1/4 | SENW | Sec | 2 | Tw | 9.0S |
| | | Rng | 15.0E | 1913 | FNL 1641 FWL |
| GPS Coord (UTM) | Surface Owner | | | | |

Participants

M. Jones (UDOGM), T. Eaton (Newfield), J. Davis (SITLA), A. Hansen (DWR).

Regional/Local Setting & Topography

This location is proposed approximately 14 road miles southwest of Myton, Utah. The topography is rolling hills and dry wash drainages. Proposed bottom hole is southeast of wellhead. This well is proposed on an existing well pad. There is no additional pad disturbance planned. The old pit area will be re-disturbed for the new pit.

Surface Use Plan**Current Surface Use**

Grazing
Wildlife Habitat

| | | | |
|-----------------------|------------------------------------|---------------------------|--------------------------|
| New Road Miles | Well Pad | Src Const Material | Surface Formation |
| 0 | Width 125 Length 310 | Onsite | |

Ancillary Facilities**Waste Management Plan Adequate?****Environmental Parameters**

Affected Floodplains and/or Wetlands N

Flora / Fauna

existing well pad.

Soil Type and Characteristics

gravely clay.

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? Y

Berm location to prevent fluids from entering and/or leaving the pad.

Erosion Sedimentation Control Required? N

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

| | | | |
|--|--------------------|----|---------------------|
| Distance to Groundwater (feet) | >200 | 0 | |
| Distance to Surface Water (feet) | >1000 | 0 | |
| Dist. Nearest Municipal Well (ft) | >5280 | 0 | |
| Distance to Other Wells (feet) | | 20 | |
| Native Soil Type | Mod permeability | 10 | |
| Fluid Type | Fresh Water | 5 | |
| Drill Cuttings | Normal Rock | 0 | |
| Annual Precipitation (inches) | 10 to 20 | 5 | |
| Affected Populations | | | |
| Presence Nearby Utility Conduits | Not Present | 0 | |
| | Final Score | 40 | 1 Sensitivity Level |

Characteristics / Requirements

Dugout earthen (80' x 40' x 8') excluded from pad dimensions.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N

Other Observations / Comments

Mark Jones
Evaluator

8/10/2011
Date / Time

Application for Permit to Drill

Statement of Basis

9/20/2011

Utah Division of Oil, Gas and Mining

Page 1

| | | | | | |
|------------------|---|---------------|--------------------------|-------------------|------------|
| APD No | API WellNo | Status | Well Type | Surf Owner | CBM |
| 4289 | 43013509090000 | SITLA | OW | S | No |
| Operator | NEWFIELD PRODUCTION COMPANY | | Surface Owner-APD | | |
| Well Name | GMBU M-2-9-15 | | Unit | GMBU (GRRV) | |
| Field | MONUMENT BUTTE | | Type of Work | DRILL | |
| Location | SENW 2 9S 15E S 1913 FNL 1641 FWL GPS Coord (UTM) | | | 568265E | 4434734N |

Geologic Statement of Basis

Newfield proposes to set 300 feet of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 250'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 2. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect useable sources of underground water.

Brad Hill
APD Evaluator

8/16/2011
Date / Time

Surface Statement of Basis

This location is proposed approximately 14 road miles southwest of Myton, Utah. The topography is rolling hills and dry wash drainages. Proposed bottom hole is southeast of wellhead. This well is proposed on an existing well pad. There is no additional pad disturbance planned. The old pit area will be re-disturbed for the new pit.

Mark Jones
Onsite Evaluator

8/10/2011
Date / Time

Conditions of Approval / Application for Permit to Drill

| | |
|-----------------|--|
| Category | Condition |
| Pits | A synthetic liner with a minimum thickness of 16 mils shall be properly installed and maintained in the reserve pit. |
| Surface | The well site shall be bermed to prevent fluids from leaving the pad. |
| Surface | Drainages adjacent to the proposed pad shall be diverted around the location. |
| Surface | The reserve pit shall be fenced upon completion of drilling operations. |


RECEIVED: September 20, 2011

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 7/29/2011**API NO. ASSIGNED:** 43013509090000**WELL NAME:** GMBU M-2-9-15**OPERATOR:** NEWFIELD PRODUCTION COMPANY (N2695)**PHONE NUMBER:** 435 646-4825**CONTACT:** Mandie Crozier**PROPOSED LOCATION:** SENW 02 090S 150E**Permit Tech Review:** ☒**SURFACE:** 1913 FNL 1641 FWL**Engineering Review:** ☒**BOTTOM:** 2377 FSL 2492 FEL**Geology Review:** ☒**COUNTY:** DUCHESNE**LATITUDE:** 40.06199**LONGITUDE:** -110.19957**UTM SURF EASTINGS:** 568265.00**NORTHINGS:** 4434734.00**FIELD NAME:** MONUMENT BUTTE**LEASE TYPE:** 3 - State**LEASE NUMBER:** ML-43538**PROPOSED PRODUCING FORMATION(S):** GREEN RIVER**SURFACE OWNER:** 3 - State**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**☒ **PLAT**☒ **Bond:** STATE/FEE - B001834☐ **Potash**☐ **Oil Shale 190-5**☐ **Oil Shale 190-3**☐ **Oil Shale 190-13**☒ **Water Permit:** 437478☐ **RDCC Review:**☐ **Fee Surface Agreement**☐ **Intent to Commingle****Commingle Approved****LOCATION AND SITING:**☐ **R649-2-3.****Unit:** GMBU (GRRV)☐ **R649-3-2. General**☐ **R649-3-3. Exception**☒ **Drilling Unit****Board Cause No:** Cause 213-11**Effective Date:** 11/30/2009**Siting:** Suspends General Siting☒ **R649-3-11. Directional Drill****Comments:** Presite Completed

Stipulations: 5 - Statement of Basis - bhill
8 - Cement to Surface -- 2 strings - hmadonald
15 - Directional - dmason
27 - Other - bhill

RECEIVED: September 20, 2011



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: GMBU M-2-9-15
API Well Number: 43013509090000
Lease Number: ML-43538
Surface Owner: STATE
Approval Date: 9/20/2011

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R. 649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Cement volumes for the 8 5/8" and 5 1/2" casing strings shall be determined from actual hole diameters in order to place cement from the pipe setting depths back to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet

- Plug and abandonment of the well – contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



For John Rogers
Associate Director, Oil & Gas

| | | |
|--|--|---|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538 |
| | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 1. TYPE OF WELL Oil Well | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 8. WELL NAME and NUMBER: GMBU M-2-9-15 |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052 | | 9. API NUMBER: 43013509090000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1913 FNL 1641 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 02 Township: 09.0S Range: 15.0E Meridian: S | | COUNTY: DUCHESNE |
| | | STATE: UTAH |

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|--|
| <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/20/2012 | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input type="text"/> |
| <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: | | | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | | | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | | | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield proposes to extend the Application for Permit to Drill for one year.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: September 13, 2012

By: 

| | | |
|---------------------------------------|------------------------------|--------------------------|
| NAME (PLEASE PRINT) Mandie Crozier | PHONE NUMBER 435 646-4825 | TITLE Regulatory Tech |
| SIGNATURE N/A | | DATE 8/31/2012 |

RECEIVED: Aug. 31, 2012



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013509090000

API: 43013509090000

Well Name: GMBU M-2-9-15

Location: 1913 FNL 1641 FWL QTR SENW SEC 02 TWP 090S RNG 150E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 9/20/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 8/31/2012

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

RECEIVED: Aug. 31, 2012

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|--|--|--|
| 1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-43538 |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 | | 7. UNIT or CA AGREEMENT NAME: GMBU |
| 4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1913 FNL 1641 FWL | | 8. WELL NAME and NUMBER: GMBU M-2-9-15 |
| OTR/OTR. SECTION, TOWNSHIP, RANGE, MERIDIAN: , 2, T9S, R15E | | 9. API NUMBER: 4301350909 |
| | | 10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT |
| | | COUNTY: DUCHESNE |
| | | STATE: UT |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|--|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLAIR |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 03/08/2013 | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/STOP) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: - Spud Notice |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 3/8/13 MIRU Pro Petro # 8. Spud well @8:00 AM. Drill 317' of 12 1/4" hole with air mist. TIH W/ 7 Jt's 8 5/8" J-55 24# csgn. Set @ 311.96. On 3/8/13 cement with 175 sks of class "G" w/ 2% CaCL2 + 0.25#/sk Cello- Flake Mixed @ 15.8ppg w/ 1.17ft3/sk yield. Returned 7 barrels cement to pit. WOC.

RECEIVED

MAR 15 2013

DIV. OF OIL, GAS & MINING

| | |
|--|------------------------|
| NAME (PLEASE PRINT) <u>Branden Arnold</u> | TITLE _____ |
| SIGNATURE <u></u> | DATE <u>03/11/2013</u> |

Casing / Liner Detail

Well GMBU M-2-9-15
Prospect GMBU
Foreman
Run Date:
String Type Conductor, 14", 36.75#, H-40, W (Welded)

- Detail From Top To Bottom -

| Depth | Length | JTS | Description | OD | ID |
|-------|--------|-----|-------------|--------|--------|
| 21.00 | | | 10' KB | | |
| 10.00 | 11.00 | | Conductor | 14.000 | 13.500 |
| 21.00 | | | - | | |

Cement Detail

| | | | | | |
|------------------------|------------|--------------|-------|--------------|--|
| Cement Company: | | | | | |
| Slurry | # of Sacks | Weight (ppg) | Yield | Volume (ft³) | Description - Slurry Class and Additives |
| | | | | | |
| | | | | | |
| | | | | | |

| | |
|--|--|
| Stab-In-Job? BHT: 0 Initial Circulation Pressure: Initial Circulation Rate: Final Circulation Pressure: Final Circulation Rate: Displacement Fluid: Displacement Rate: Displacement Volume: Mud Returns: Centralizer Type And Placement: | Cement To Surface? Est. Top of Cement: Plugs Bumped? Pressure Plugs Bumped: Floats Holding? Casing Stuck On / Off Bottom? Casing Reciprocated? Casing Rotated? CIP: Casing Wt Prior To Cement: Casing Weight Set On Slips: |
|--|--|

Casing / Liner Detail

Well GMBU M-2-9-15
Prospect GMBU
Foreman
Run Date:
String Type Surface, 8.625", 24#, J-55, STC (Generic)

- Detail From Top To Bottom -

| Depth | Length | JTS | Description | OD | ID |
|--------|--------|-----|--------------|-------|----|
| 311.96 | | | 10' KB | | |
| 10.00 | 1.42 | | Wellhead | | |
| 11.42 | 255.33 | 6 | 8 5/8 casing | 8.625 | |
| 266.75 | 44.24 | 1 | Shoe Joint | 8.625 | |
| 310.99 | 0.97 | | Guide Shoe | | |
| 311.96 | | | - | | |

Cement Detail

| | | | | | |
|------------------------------|------------|--------------|-------|--------------|--|
| Cement Company: Other | | | | | Description - Slurry Class and Additives |
| Slurry | # of Sacks | Weight (ppg) | Yield | Volume (ft³) | |
| Slurry 1 | 175 | 15.8 | 1.17 | 204.75 | Class G+2%kcl+.25#CF |

| | |
|--|-------|
| Stab-In-Job? | No |
| BHT: | 0 |
| Initial Circulation Pressure: | |
| Initial Circulation Rate: | |
| Final Circulation Pressure: | |
| Final Circulation Rate: | |
| Displacement Fluid: | Water |
| Displacement Rate: | |
| Displacement Volume: | 16.4 |
| Mud Returns: | |
| Centralizer Type And Placement: | |
| Middle of first, top of second and third for a total of three. | |

| | |
|-------------------------------|------|
| Cement To Surface? | Yes |
| Est. Top of Cement: | 0 |
| Plugs Bumped? | Yes |
| Pressure Plugs Bumped: | 475 |
| Floats Holding? | No |
| Casing Stuck On / Off Bottom? | No |
| Casing Reciprocated? | No |
| Casing Rotated? | No |
| CIP: | 9:55 |
| Casing Wt Prior To Cement: | |
| Casing Weight Set On Slips: | |

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM -FORM 6

OPERATOR: **NEWFIELD PRODUCTION COMPANY**
ADDRESS: **RT. 3 BOX 3630**
MYTON, UT 84052

OPERATOR ACCT. NO. **N2695**

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|----------------|-----------------------|-------------------|-------------------|----------------------|---------------|----------|-----------|------------|-----------------|-----------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 99999 | 17400 | 4301350909 | GMBU M-2-9-15 | SENW | 2 | 9S | 15E | DUCHESNE | 3/7/2013 | 3/28/13 |

WELL 1 COMMENTS:

| ACTION B | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|-------------|-----------------------|-------------------|-------------------|----------------------|---------------|----------|-----------|------------|-----------------|-----------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 99999 | 17400 | 4301350908 | GMBU H-2-9-15 | SENW | 2 | 9S | 15E | DUCHESNE | 3/7/2013 | 3/28/13 |


| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|----------------|-----------------------|-------------------|-------------------|-----------------------------|---------------|-----------|-----------|-----------|---------------|-----------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| A | 99999 | 18958 | 4304752028 | UTE TRIBAL 5-21-4-2E | SWNE | 21 | 4S | 2E | UINTAH | 3/5/2013 | 3/18/13 |

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|----------------|-----------------------|-------------------|-------------------|----------------------|---------------|----------|-----------|------------|-----------------|-----------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 99999 | 17400 | 4301351049 | GMBU J-5-9-17 | SWNW | 4 | 9S | 17E | DUCHESNE | 3/9/2013 | 3/28/13 |

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|----------------|-----------------------|-------------------|-------------------|----------------------|---------------|----------|-----------|------------|-----------------|-----------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| B | 99999 | 17400 | 4301351048 | GMBU O-4-9-17 | SWNW | 4 | 9S | 17E | DUCHESNE | 3/8/2013 | 3/28/13 |

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|----------------|-----------------------|-------------------|-------------------|-----------------------------|---------------|----------|-----------|-----------|---------------|------------------|-------------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| A | 99999 | 18982 | 4304752019 | UTE TRIBAL 15-9-4-1E | SWSE | 9 | 4S | 1E | UINTAH | 3/13/2013 | 3/28/13 |

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)


Signature
Tabitha Timothy
Production Clerk 03/18/13

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED
MAR 18 2013
Div. of Oil, Gas & Mining

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538 |
| 1. TYPE OF WELL Oil Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: GMBU M-2-9-15 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1913 FNL 1641 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 02 Township: 09.0S Range: 15.0E Meridian: S | | 9. API NUMBER: 43013509090000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: MONUMENT BUTTE |
| COUNTY: DUCHESNE | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 4/30/2013 | <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> The above well was placed on production on 04/30/2013 at 11:00 hours. Production Start sundry re-sent on 09/12/2013. </div> <div style="width: 35%; text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 13, 2013 </div> </div> | | |
| NAME (PLEASE PRINT) Jennifer Peatross | PHONE NUMBER 435 646-4885 | TITLE Production Technician |
| SIGNATURE N/A | DATE 9/12/2013 | |



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

November 28, 2016

CERTIFIED MAIL NO.: 7015 0640 0003 5276 0440

Mr. Kirby Carroll
Newfield Production Company
1001 17th Street, STE 2000
Denver, CO 80202

43 013 50909
GMBU M-2-9-15
2 95 15E

Subject: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases

Dear Mr. Carroll:

As of August 2016, Newfield has thirty-two (32) State and Fee Lease Wells (see attachment A) that are currently in non-compliance with the requirements for extended shut-in or temporarily abandoned (SI/TA) status.

Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas and Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).

Please note that the Divisions preferred method for showing well integrity is by MIT.



Page 2
Newfield Production Company
November 28, 2016


Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

All Submittals should be sent via ePermit

If the required information is not received within 30 days of the date of this notice, further actions may be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet
Petroleum Engineer

DKD/DD/js

cc: Compliance File
Well File
LaVonne Garrison, SITLA

N:\O&G Reviewed Docs\ChronFile\PetroleumEngineer\SITA

ATTACHMENT A

| | Well Name | API | LEASE | Years.Months Inactive |
|------|-----------------------------|--------------|----------|-----------------------|
| 1 | GMBU 2-16-9-18H | 43-047-52013 | ML-48378 | 4.4 |
| 2 | Gulf State 36-13 | 43-047-31345 | ML-22057 | 9.2 |
| 3 | Moon 3-20-4-2 | 43-013-50007 | Fee | 3.5 |
| 4 | S Mon Butte ST P-2-9-16 | 43-013-50118 | ML-21839 | 3.6 |
| 5 | State 3-16-9-18 | 43-047-35813 | ML-48378 | 3.5 |
| 6 | Wells Draw ST 7-36 | 43-013-30934 | ML-21835 | 3.4 |
| 7 | Prewitt 10-24 | 43-013-31865 | Fee | 3.2 |
| 8 | W Draw ST N-32-8-16 | 43-013-34146 | ML-45555 | 2.4 |
| 9 | Wells Draw 2-32-8-16 | 43-013-32220 | ML-21836 | 2.3 |
| 10 | GMBU N-2-9-15 | 43-013-50910 | ML-43538 | 2.2 |
| → 11 | GMBU M-2-9-15 | 43-013-50909 | ML-43538 | 2.1 |
| 12 | Moon 1-29-4-2 | 43-013-50006 | Fee | 2.0 |
| 13 | Moon 1-20-4-2 | 43-013-50008 | Fee | 2.0 |
| 14 | State 1-36-8-15 | 43-013-34234 | ML-21835 | 2.5 |
| 15 | Ashley ST 6-2-9-15 | 43-013-32584 | ML-43538 | 1.10 |
| 16 | Allen Trust 2-24 | 43-013-31944 | Fee | 1.9 |
| 17 | Lamb 4-34-4-1E | 43-047-40272 | Fee | 1.5 |
| 18 | Wells Draw 4-32-8-16 | 43-013-32222 | ML-21836 | 1.8 |
| 19 | Greater Mon Butte T-36-8-16 | 43-013-50211 | ML-22061 | 1.8 |
| 20 | Williams #14-8-4-2 | 43-013-50617 | Fee | 1.8 |
| 21 | Hancock 11-21-4-1 | 43-013-33242 | Fee | 1.5 |
| 22 | Malnar 9-19-4-1 | 43-013-33913 | Fee | 1.2 |
| 23 | Hancock 16-20-4-1 | 43-013-33914 | Fee | 1.0 |
| 24 | State 12-36-8-15 | 43-013-34224 | ML-21835 | 2.1 |
| 25 | State 4-36-8-15 | 43-013-34231 | ML-21835 | 1.4 |
| 26 | Roberts 4-19-4-1 | 43-013-50072 | Fee | 1.1 |
| 27 | Mon Butte East K-36-8-16 | 43-013-50112 | ML-22061 | 1.1 |
| 28 | S Mon Butte ST N-2-9-16 | 43-013-50117 | ML-21839 | 1.4 |
| 29 | Wilcken 16-23-4-2 | 43-013-50304 | Fee | 1.0 |
| 30 | Hancock 12-7-4-1W | 43-013-50422 | Fee | 1.3 |
| 31 | State 1-16-9-18 | 43-047-35811 | ML-48378 | 1.6 |
| 32 | Lamb 1-34-4-1E | 43-047-40275 | Fee | 1.1 |



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 14, 2016

CERTIFIED MAIL NO.: 7015 0640 0003 5276 0525

Ms. Assiya Bekniyazova
Newfield Production Company
4 Waterway Square PL, STE 100
The Woodlands, TX 77380

43 013 50909
GMBU M-2-9-15
2 9S 15E

Subject: Extended Shut-in and Temporary Abandoned Well Requirements for Fee or State Leases

Dear Ms. Bekniyazova:

As of August 2016, Newfield has thirty-two (32) State and Fee Lease Wells (see attachment A) that are currently in non-compliance with the requirements for extended shut-in or temporarily abandoned (SI/TA) status.

Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas and Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and
3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).

Please note that the Divisions preferred method for showing well integrity is by MIT.



Page 2
Newfield
December 14, 2016

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

All Submittals should be sent via ePermit

If the required information is not received within 30 days of the date of this notice, further actions may be initiated. If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet
Petroleum Engineer

DKD/DD/js

cc: Compliance File
Well File
LaVonne Garrison, SITLA

N:\O&G Reviewed Docs\ChronFile\PetroleumEngineer\SITA

ATTACHMENT A

| | Well Name | API | LEASE | Years.Months Inactive |
|------|-----------------------------|--------------|----------|-----------------------|
| 1 | GMBU 2-16-9-18H | 43-047-52013 | ML-48378 | 4.4 |
| 2 | Gulf State 36-13 | 43-047-31345 | ML-22057 | 9.2 |
| 3 | Moon 3-20-4-2 | 43-013-50007 | Fee | 3.5 |
| 4 | S Mon Butte ST P-2-9-16 | 43-013-50118 | ML-21839 | 3.6 |
| 5 | State 3-16-9-18 | 43-047-35813 | ML-48378 | 3.5 |
| 6 | Wells Draw ST 7-36 | 43-013-30934 | ML-21835 | 3.4 |
| 7 | Prewitt 10-24 | 43-013-31865 | Fee | 3.2 |
| 8 | W Draw ST N-32-8-16 | 43-013-34146 | ML-45555 | 2.4 |
| 9 | Wells Draw 2-32-8-16 | 43-013-32220 | ML-21836 | 2.3 |
| 10 | GMBU N-2-9-15 | 43-013-50910 | ML-43538 | 2.2 |
| → 11 | GMBU M-2-9-15 | 43-013-50909 | ML-43538 | 2.1 |
| 12 | Moon 1-29-4-2 | 43-013-50006 | Fee | 2.0 |
| 13 | Moon 1-20-4-2 | 43-013-50008 | Fee | 2.0 |
| 14 | State 1-36-8-15 | 43-013-34234 | ML-21835 | 2.5 |
| 15 | Ashley ST 6-2-9-15 | 43-013-32584 | ML-43538 | 1.10 |
| 16 | Allen Trust 2-24 | 43-013-31944 | Fee | 1.9 |
| 17 | Lamb 4-34-4-1E | 43-047-40272 | Fee | 1.5 |
| 18 | Wells Draw 4-32-8-16 | 43-013-32222 | ML-21836 | 1.8 |
| 19 | Greater Mon Butte T-36-8-16 | 43-013-50211 | ML-22061 | 1.8 |
| 20 | Williams #14-8-4-2 | 43-013-50617 | Fee | 1.8 |
| 21 | Hancock 11-21-4-1 | 43-013-33242 | Fee | 1.5 |
| 22 | Malnar 9-19-4-1 | 43-013-33913 | Fee | 1.2 |
| 23 | Hancock 16-20-4-1 | 43-013-33914 | Fee | 1.0 |
| 24 | State 12-36-8-15 | 43-013-34224 | ML-21835 | 2.1 |
| 25 | State 4-36-8-15 | 43-013-34231 | ML-21835 | 1.4 |
| 26 | Roberts 4-19-4-1 | 43-013-50072 | Fee | 1.1 |
| 27 | Mon Butte East K-36-8-16 | 43-013-50112 | ML-22061 | 1.1 |
| 28 | S Mon Butte ST N-2-9-16 | 43-013-50117 | ML-21839 | 1.4 |
| 29 | Wilcken 16-23-4-2 | 43-013-50304 | Fee | 1.0 |
| 30 | Hancock 12-7-4-1W | 43-013-50422 | Fee | 1.3 |
| 31 | State 1-16-9-18 | 43-047-35811 | ML-48378 | 1.6 |
| 32 | Lamb 1-34-4-1E | 43-047-40275 | Fee | 1.1 |